Task Description	Data				Model			
	Sample	Size	Annotations	Source	Algorithm	Architecture	Performance	Ref
Segmentation of Vegetation near Power Lines		5 Images 800 x 800 x 3 + 10 Images 400 x 400 x 3 26 km PL Length	1 Class Unspecified Pixels Num.	Not Available	Supervised ML + DL	FE + MLP + Custom CNN	F1 = 72.17%	[77]
Segmentation of Vegetation and Power Lines		532 Images 256 x 256 x 3 2.4 km PL Length	2 Classes Unspecified Pixels Num.	Openly Available [203]	Supervised DL	Unet +BCE	mIoU = 66.35%	[204]
					Supervised DL	DeepLab + Tversky	mIoU = 68.25%	[204]
Foreign Object Detection near Power Lines		14,615 images from 1920 x 1080 x 3 to 2048 x 2048 x 3	4 Classes 40,541 B. Box Num.	Code + Data Openly Available [205], [206]	Supervised DL	YOLOv8-l	mAP50 = 94.2%	[207]
					Supervised DL	YOLOv6-s	mAP50 = 93.9%	[207]
Foreign Object Detection Obstructing Utility Assets		3,140 Original Images Unspecified Resolution	9 Classes Unspecified B. Box Num.	Not Available	Supervised DL	YOLOv5-l 1280 input	mAP50 = 86.39%	[208]
					Supervised DL	YOLOv5-x 640 input	mAP50 = 85.43%	[208]